Hillview Rise GLS Site

Briefing Session 25 Jan 2018



Note:


For the purpose of fairness and transparency, there will be no Q&A session. You may send in your questions through <u>URA's online feedback and enquiry form</u>. All questions and answers will be consolidated and published at a later date.

Ho Xue Mei Executive Manager Construction Productivity and Quality Group Building and Construction Authority



Construction Industry Transformation Map

- Launched in October 2017
- Developed in close
 partnership with industry, trade associations and chambers (TACs), institutes of higher learning (IHLs), unions and government
- Aim to achieve a future-ready built environment with smart, green and high quality buildings



Vision - Transforming the BE sector

3 Key Areas to Transform the Sector

Design for Manufacturing & Assembly (DfMA)



Design upfront for ease of manufacturing and assembly



Highly automated offsite production facilities



Efficient and clean on-site installation process

Green Buildings



Design for Green Buildings



Sustainable practices in operations and maintenance

Integrated Digital Delivery (IDD)



Enabled by Building Information Modelling (BIM), IDD fully integrates processes and stakeholders along the value chain through advanced info-communications technology (ICT) and smart technologies.


Vision - Transforming the BE sector

Increase adoption of DfMA and IDD

- Establish robust DfMA ecosystem to make DfMA price competitive and enable widespread adoption
- Develop IDD shared platforms and standards to support the adoption of IDD solutions

Build strong and capable firms


 Encouraging greater collaboration among firms



Hillview Rise GLS Site - Concept and Price


Rationales for piloting at Hillview Rise

- Sizeable (535 residential units) site suitable as a pilot site to benchmark productivity outcomes
- Greater scope for modularization and economies of scale to optimize productivity gains
- Purely residential site without the complexity of other usage requirements
- Suitable for piloting new innovative technologies



Concept and Price Tender

- Tenders will be evaluated based on concept proposal and tendered sale price.
- Concept Evaluation Committee (CEC), chaired by BCA
 - First evaluate the Concept Proposals
 - Only Concept Proposals that substantially satisfy the evaluation criteria will be shortlisted for the 2nd stage of the tender evaluation
- Tender Evaluation Committee (TEC)
 - Open the price envelopes of shortlisted tenders
 - Tender with the highest tendered sale price will be considered for award
- After tender award, the concept proposal will still be required to be reviewed by a Construction Productivity Advisory Panel (CPAP).



Construction Productivity Plan

75%


1 Overall construction productivity concept

- Adoption of Design for Manufacturing and Assembly (DfMA) concept to achieve the highest productivity outcomes possible.
- Productivity outcomes should be comparable to or better than the most advanced method of DfMA technologies adopted at GLS sites
- 2 Level of prefabrication and integration across architectural, structural, mechanical, electrical and plumbing (MEP) works
- Overall building design (architectural finishing, MEP works) should support the implementation of the proposed advanced construction technologies and support the functional requirements of the building.
- Design and modularisation of building and floor layouts should achieve high levels
 of integration in the construction of the architectural, structural and MEP works.
- Structural system should incorporate highly productive construction technologies and demonstrate the extent of implementation of the proposed technologies.
- MEP works should be planned, executed and integrated upfront with all other trades in design, prefabrication and installation.
- Feature innovative proposals to support the Construction Productivity Plan.

Design for Manufacturing and Assembly (DfMA)

Aim

- Move traditional construction work offsite into controlled factory environment
- Move designs upfront for ease of manufacturing and assembly to improve quality and productivity





Local DfMA Projects

NTU North Hill Hostel

Time savings 2 months

Manpower savings (project level)

17%



Number of Storeys	13 (6 blocks)
Number of Rooms	1580
Number of Modules	1200

Crowne Plaza Extension

Time savings 6 months

Manpower savings (project level)

44%



Numbe	r of Storeys	10
Numbe	r of Rooms	243
Numbe	r of Modules	252

NTU Nanyang Crescent Hostel

Time savings 6 months

Manpower savings (project level)

25%



Number of Storeys	11 to 13 (4 blocks)
Number of Rooms	1527
Number of Modules	784

MOHH Nursing Home

Time savings 3 months
Manpower savings (project level)

24%



Number of Storeys	9
Number of Units	180
Number of Modules	343

Local PPVC Projects

Brownstone EC @ Canberra

Time savings 4 months *(estimated)*Manpower savings (project level) 20% *(estimated)*



Number of Storeys	10/12 (8 blocks)
Number of Units	638
Number of Modules	4384

The Clement Canopy (GLS)



Number of Storeys	40
Number of Units	505
Number of Modules	1866

Ongoing construction
Over 20 storey completed



7 day installation cycle/floor

Construction Management Plan

15%

- 3 Effective project scheduling, monitoring and productivity tracking methodologies
- Adopt Building Information Modelling (BIM) and other methodologies to track project progress, identify and address potential sources of delay upfront, so as to ensure that the project is on schedule.

- 4 Effective project integration and collaboration approach
- Adopt Virtual Design and Construction (VDC) and other methodologies to achieve integration across the project value chain from design through manufacturing to construction.
- Incorporate an integrated project delivery approach such as Design and Build or Design Development and Build.
- Feature innovative proposals to support the Construction Management Plan.

Integrated Digital Delivery (IDD)


Aim

Connect various industry parties involved in building and construction projects through digital information

Digital Design

e.g. WOHA (Kampung Admiralty)

- ✓ BIM to improve constructability
- ✓ Use of **visual scripting** to automate certain mundane tasks (e.g. sheet creation)



Digital Manufacturing and Fabrication (off-site)

e.g. Greyform

✓ BIM-to-Production
 methodology translate
 BIM models into modules
 to be installed onsite



Digital Construction (on-site)

e.g. Kimly + Pre-caster + NTU

- ✓ Modules are trackable at all times
- ✓ Automatically stored/ installed
- ✓ Travel via a 'ideal' path (e.g. least distance)



Digital Asset Delivery and Management

e.g. CCDC (for High Park Residences)

- ✓ Quality and defects management system
- Handover asset data through BIM



Track Record

10%

5	Track Record	• The tenderer/developer and project teams will be assessed based on their relevant skills and/or experience in employing advanced construction technologies for residential developments, with proven track records (which may include productivity, quality and safety) both locally and overseas.	
		 Tenderers/developer and project teams with only overseas projects may substantiate their track records with relevant international construction awards or accolades, where applicable. 	

Tender Submission Requirements

8 sets in A3 format

Hardcopy Concept Proposal Construction Productivity Plan (<30 pages)

Construction Management Plan (<5 pages)

Track Record (<5 pages)
+ Appendix 1 (sample)

2 sets in CD/DVD-ROM/USB3.0 or latest format

Soft Copies

Concept Proposal (PDF)

Video animation (max. 5 min)

Tender Evaluation Process

Tender Closing

3 May 2018 (before 12 noon)

The URA Centre
Tender Box, Room 10-1

Presentation of Concept Proposal to Concept Evaluation Committee (CEC)

7 and 8 June 2018

Successful Tenderer

Reflect the Concept Proposal in a Productivity Concept Implementation Plan (PCIP)

Stage 1
Before submission of development application to URA

Accepted PCIP

Seek <u>in-principle acceptance</u> (IPA) of the PCIP from the Construction Productivity Advisory Panel (CPAP)

Stage 2
During application for BP and ST clearance to BCA

*Approved PCIP

Seek <u>approval</u> of the accepted PCIP from the Commissioner of Building Control

*In accordance to the Building Control (Buildability and Productivity) Regulations 2011.

Hillview Rise GLS Site

Thank you.



Note:

For the purpose of fairness and transparency, there will be no Q&A session. You may send in your questions through <u>URA's online feedback and enquiry form</u>. All questions and answers will be consolidated and published at a later date.

Ho Xue Mei
Executive Manager
Construction Productivity and Quality Group
Building and Construction Authority

